## Marine and Coastal Access Act 2009 (Part 4 Marine Licensing)

#### Application for Marine Construction Works/Land Reclamation/Beach Replenishment in the Territorial Sea and UK Controlled Waters Adjacent to Northern Ireland

(Construction schemes including coast defences, beneficial uses of dredged materials, jetties, land reclamation, outfall pipes etc.)

## It is the responsibility of the applicant to obtain any other consents or authorisations that may be required

Under Part 4 (Chapter 5) of the Marine and Coastal Access Act 2009, information contained within or provided in support of this application will be placed on the public register unless DAERA Marine and Fisheries Division (as the licensing authority) approves the applicant's reasons for withholding all or part thereof.

#### Public Register

Is there any information contained within or provided in support of this application that you consider should not be included on the Public Register on the grounds that its disclosure:

a) would be contrary to the interests of national security	YES	_ NO [	$\checkmark$	
--	-----	--------	--------------	--

NO

 b) would prejudice to an unreasonable degree your or some other person's commercial interests or those of a third party? YES

If **YES**, to either (a) or (b), please provide full justification as to why all or part of the information you have provided should be withheld.

N/A

## 1. Project Title

Please give a brief identifiable description, including the location of the works.

NIR Minor Works 2016 – 2020 ELR 010 – River Faughan 10.220 (89m 1254yds) Northern Ireland Railways (NIR) requires essential infrastructural maintenance on the Belfast to Derry line at The River Faughan. The proposed works involve the extension of existing scour prevention measures which have recently deteriorated. Site location plan attached at Appendix A.

## 2. Applicant Details

Title	MR	Initials	А.	Surname	STOVE							
Addres	SS:		Translink Property & Structures Department 3 Milewater Road Belfast BT3 9BG									
Name (if diffe	of contact: erent from ab	ove)	N/A									
Teleph (inc. co	none number ode)	ï	(028) 9035 4075									
Email	address:		anthony.stov	uk								

# 3. Agent Details (if appropriate)

Title	MR	Initials	G.	Surname	MCCORMACK							
Tradin (If diffe	g Title erent from ab	oove)	AECOM Infrastructure & Environment UK Ltd									
Busine	ess Address:		9 <sup>th</sup> Floor, The Clarence West Building, Clarence Street West, Belfast, BT2 7GP									
Name (if diffe	of contact: erent from ab	oove)		N/A								
Positic (if app	on within con ropriate)	npany	Civil Engineer									
Teleph (inc. co	none number ode)	r:	(028) 9060 7200									
Email	address:			ormack@aecom.com								
Compa	any Registra	tion No.	00880328									

# 4. Duration of Project

Expected Start Date

29th Jan	
2019	

Expected Completion Date



## 5. Description and Cost of the Proposed Project

(a) Estimated gross cost of the works proposed seawards of the tidal limit of the High Water Mean Spring Tide Mark

The estimated gross cost of the works at The River Faughan is £30,000.

Licence Band B – Fee £859

(b) Give a detailed description of the proposed schedule of work

The works comprise extending/replacing existing continuous sheet piling around the perimeter of Piers 7 & 9, which have become undermined. Loose sediment to be excavated between sheet piles and existing pier/footing and filled with tremmied concrete. Timber posts and metal brackets at Piers 3 & 8 to be removed. Scour erosion at the upstream nose of Piers 5 & 8 to be repaired. Minor defects to the surface of the concrete piers at upstream end of Piers 3, 4, 6 & 8 to be repaired. Cylindrical cores extracted from piers to be repaired with filler.

Drawings detailing the existing bridge and proposed repair works are included in Appendix B.

MHWS – 3.5 m Admirality Chart Datum (ACD)

If necessary please continue on a separate sheet and tick this box



Types of Work Proposed

Coastal/Flood defences:	beach replenishment						
	shoreline reinforcement						
	flood defence						
	sea defence						
Slipways:	slipway						
	causeway						
	launching ramp						
Miscellaneous:	habitat creation/replacement						
	aquaculture (unless exempted)						
	sea wall						
	berms/wave screens						
	artificial reef						
	sea-lock						
Harbour works:	dock wall/quay/wharf						
Navigation works:	lock gates						
	moorings (unless exempted)						
	buoy/navigation mark (unless exempted)						
	training wall/breakwater						
Land reclamation:	bunded/piled area						
	dock infill						
Intakes/outfall pipes:	intake/outfall						
Cables:	cable/subsea cable						
Pipeline maintenance:	pipe/pipeline maintenance						
Piers etc.:	bridge supports/bridge foundation						
	pier						
	jetty						
Bank stabilisation:							

Scour protection:

Barrages & island etc.

# Sheet

# **Piling**

mattressing tidal barrier barrage sculpture, statues, fountains etc. ground investigation works impoundment groynes

### 6. Location of Works

Sediment manipulation

This should include either 6 figure Irish Grid Reference (IGR) or Latitude and Longitude co-ordinates (WGS84 to 1 decimal minute) defining the extent of the project.

Irish Grid Reference (IGR) 248921,422498 MHWS – 3.5m Admirality Chart Datum (ACD)

Location Plan Drawing is provided in Appendix A.

If necessary, please continue on a separate sheet and tick this box

## 7. Method Statement

#### All works will be performed at night.

- 1. It is intended that the piling works will be carried out from a barge anchored underneath the bridge structure.
- 2. This barge will be floated into position and anchored by works boats at high tide.
- 3. Works in relation to piling will be carried out during daylight hours using a Movac excavator to drive the piles.
- 4. Piles are to be driven before the barge is to be relocated to allow the piles to be placed around the pier.
- 5. On completion the barge will move to the next pier until the piling is complete.
- 6. All concreting works will be carried out from the track and during night shift hours.
- 7. Rail Road Vehicle (RRV) operator under the direction of the banksman is to lift the trailer onto the tracks using the chains. Equipment to go to site is to be loaded onto the trailer, this includes a tower light and concrete skip.
- 8. Concrete Lorries will deliver concrete to both Du Pont and Lock Level Crossings, filling up the concrete skip on each RRV.
- 9. Skilled operatives working with subcontractor from the barge will position the tremmie pipe to deploy concrete between the sheet piles and the pier at pier 7 and pier 9.
- 10. When the concrete skip is empty the RRV will return to its concrete lorry to refill the concrete skip and the other RRV will travel to site and deploy concrete in the same manner.
- 11. RRVs will alternate until all concrete has been poured up to the level of the concrete pier footing.
- 12. Subcontractor to remove timber posts and metal brackets from piers 3 and 8 using the barge to access the piers.
- 13. Subcontractor to remove tree debris from the nose of pier 3 and dispose of it off site.
- 14. Excess vegetation to be removed from the West abutment using a chainsaw, hand tools, strimmer's and hedge cutters. Arising's to be disposed of offsite.
- 15. Exposed rebar to be trimmed back on the East abutment using the power saw.
- 16. Scour erosion to be repaired on upstream nose of piers 5 and 8 as outlined in AECOM Drawing No. 60512590-1007-10022-2 Rev A2 detail Type 1 Repair.
- 17. Defects to concrete surface of previous concrete patch repairs on piers 3, 4, 6 and 8 to be repaired according to detail Type 1 Repair.
- 18. Damaged concrete will be carefully removed from around reinforcement, reinforcement bars to be cleaned of rust and corrosion and painted with Galvafroid or similar and have a surface finish of SA 2.5.
- 19. The exposed concrete repair surface will be treated with a suitable acrylic primer.
- 20. Cementitious repair mortar Fosroc Renderoc GP to be used to fill repair area to its extents and create a flush finish. Overhead repair work to be built up in layers to prevent material falling out.
- 21. As indicated by the onsite engineer some areas will receive L shaped dowel anchors, these will have holes drilled for the dowel bars which are to be set in with a chemical anchor before proceeding with the concrete repair.
- 22. Cementitious polymer coating to be applied to the concrete surface up to 3mm thick if requested by onsite engineer.
- 23. At the end of the shift all plant will be removed.
- 24. The Foreman will ensure that the site has been left clear and tidy.

If necessary, please continue on a separate sheet and tick this box

## 8. Permanent Deposits

(a) quantity of permanent materials to be deposited below HMWS tidemark:

Timber (m <sup>2</sup> or tonnes)	
Iron/Steel (tonnes)	14
Plastic/Synthetic (m <sup>2</sup> )	
Silt (m <sup>3</sup> )	
Sand (m <sup>3</sup> )	
Concrete (m <sup>3</sup> )	11.2
Concrete bags/mattresses (Confirm number, dimensions & total volume m <sup>3</sup> ) Stone/ <mark>Rock</mark> /Gravel (size range and volume m <sup>3</sup> )	

If 'other' please describe below

N/A

If necessary, please continue on a separate sheet and tick this box

(b) for work involving salt marsh feeding, beach replenishment or land reclamation please provide the following information relating to the material to be deposited:

Quantity (tonnes)	
Nature of Material (e.g. sand, silt, gravel etc.)	
Source: (if sea dredged please state location of origin)	
Particle Size	

Has the material been chemically analysed? Yes No

If Yes, please include the analysis data with your application.

## 9. Temporary Deposits

Will there be a need to make any temporary deposits of material below HMWS tidemark during the works

Yes		No	~	
-----	--	----	---	--

(a) quantity of temporary materials to be deposited below HMWS tidemark:

Timber (m <sup>2</sup> or tonnes)	
Iron/Steel (tonnes)	
Plastic/Synthetic (m <sup>2</sup> )	
Silt (m <sup>3</sup> )	
Sand (m <sup>3</sup> )	
Concrete (m <sup>3</sup> )	
Concrete bags/mattresses (Confirm number, dimensions & total volume m <sup>3</sup> )	
Stone/Rock/Gravel (size range and volume m <sup>3</sup> )	

If 'other' please describe below

If necessary, please continue on a separate sheet and tick this box

## 10.Dredging

Do you intend to apply for a licence to dredge as part of the works?

Yes No
--------

#### 11. Disposal of Material at Sea

Do you intend to apply for a licence to dispose at sea material dredged as part of the works?

Yes	No	$\checkmark$
100		

If Yes, please indicate: Nature and quantity of material (sand, gravel, silt, clay, rock etc.)

| <br> |  |      | <br> |       |
|------|------|------|------|------|------|------|------|------|------|--|------|------|-------|
| <br> |  | <br> | <br> | <br>- |

#### 12. Planning

Is this project subject to a planning application?

Yes		No	$\checkmark$	
-----	--	----	--------------	--

If Yes, attach a copy of environmental statement (if appropriate) and indicate what stage the application for planning permission is at (i.e. approved, awaiting notification, rejected)

.....

#### **13. Statutory Consenting Powers**

Do you, or (if appropriate) your client, have statutory powers to consent any aspect of this project?

Yes No	v
--------	---

If Yes, please give details

#### 14. Consultation

(a) Have the public been invited to submit comments? YES If YES, how and where?

NO	

	N/A		
(b)	Have any consultation meetings been held? (with the public or other bodies)	YES	NO 🗸

If necessary please continue on a separate sheet and tick this box

#### **15.**Consultation with Conservation Bodies

N/A

Please provide details of any consultation that has taken place with NIEA Natural Environment Division and, if appropriate, include copies of any correspondence with your application.

Agencies notified include Rivers Agency, Loughs Agency (Section 46/47 Permit), Fisheries (Section	
48 Permit) & NIEA	
A Habitats Regulations Assessment (HRA) has been prepared to support the application.	

If necessary please continue on a separate sheet and tick this box

## 16. Designated Conservation Areas

Are any parts of the	proposed work lo	cated within the	boundaries of a designated
conservation area?	YES 🗸	NO	]

If <b>No</b> , please indicate approximate distance of the disposal	
operation from the nearest designated conservation area.	

## **17. Environmental Assessment**

Has an environmental assessment been undertaken to support any application in respect of the works,

your own statutory powers (if applicable) or any other reason?

If **YES**, is a copy of the assessment included with this YES application?

If the assessment has been undertaken but has not been included with the application, please provide an explanation below.

Is the environmental assessment available for public inspection?

YES

NO

NO

 $\checkmark$ 

NO ~

If YES at what locations:

N/A

N/A

## Declaration

I declare that the information given in this form and related papers is to the best of my knowledge and belief true.

## WARNING

It is an offence under the Act under which this application is made to fail to disclose information or to provide false or misleading information.

Signature of applicant: (or agent acting on behalf of applicant)



Date:

GRAHAM MCCORMACK

20/08/2018

Name (Block Letters):

Position within company: (if applicable)

**Civil Engineer** 

## PLEASE CHECK CAREFULLY THE INFORMATION YOU HAVE GIVEN AND THAT ALL ENCLOSURES (INCLUDING COPIES) HAVE BEEN INCLUDED

## **Application Checklist**

- Completed application form
- Project drawings
- Method statement
- Maps/charts
- Additional environmental information e.g. photographs, environmental impact assessment etc.
- Payment

Appendix A

47075660 - 10.220 - 01 - Site Location

Plot Date : 12/17/2015 5:02 PM



Appendix B

60512590 - 1007 - 10022-1 Undew ater Repais 60512590 - 1007 - 10022-2 Undew ater Repais



#### SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION BOX IT IS ASSUMED THAT ALL WORKS ON THIS DRAWING WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROPRIATE METHOD STATEMENT. Schedule of Repairs THIS DRAWING IS TO BE USED ONLY FOR THE PURPOSE OF ISSUE THAT IT WAS ISSUED FOR AND IS SUBJECT TO AMENDMENT. 1. Sheet pile around full perimeter of NOTES THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT undermined piers 7 & 9, in DOCUMENTATION. DO NOT SCALE FROM THIS DRAWING, USE ONLY PRINTED DIMENSIONS. accordance with Sheet Piling notes ALL DIMENSIONS IN MILLIMETRES, ALL CHAINAGES, LEVELS AND COORDINATES ARE IN METRES UNLESS DEFINED OTHERWISE. (Photos 1 & 2). THIS DRAWING IS TO BE READ IN CONJUNCTION WITH THE PROJECT HEALTH & SAFETY FILE FOR ANY IDENTIFIED POTENTIAL RISKS. DE-VEGETATION 2. Remove timber post and metal CUT BACK VEGETATION GROWTH OBSCURING FACE OF ABUTMENTS / WING brackets fitted to bridge piers 3 & 8 WALLS / RIVER WALLS, INCLUDING ANY OVERHANGING VEGETATION. CUTTINGS SHALL BE REMOVED AND DISPOSED OF OFF-SITE. MORTAR JOINTS (Photo 3 shows typical defect) SHALL BE FREE OF VEGETATION (SEE RE-POINTING NOTES BELOW). TREE GROWTH SHALL BE CUT BACK AND ROOTS KILLED-OFF BY DRILLING HOLES IN ROOTS AND INJECTING WITH A SUITABLE HERBICIDE. Remove tree branch debris trapped SHEET PILING at the upstream nose of Pier 3 SHEET PILING DESIGN, INCLUDING PILE SPECIFICATION, MINIMUM EMBEDMENT DEPTH AND TEMPORARY STABILITY MEASURES, SHALL BE (Photo 4) PROVIDED BY PILING CONTRACTOR AND SUBMITTED TO NIR FOR APPROVAL SHEET PILES SHALL BE EMBEDDED SUFFICIENTLY BELOW EXISTING BED Repair scour erosion at upstream LEVEL TO MITIGATE AGAINST FUTURE SCOUR ACTION. nose of Piers 5 & 8 in accordance ONCE SHEET PILES ARE INSTALLED AND FULLY CLUTCHED AROUND THE PERIMETER OF THE PIER FOOTING, BED MATERIAL BETWEEN THE with Concrete Repair Detail - see SHEET PILING AND THE PIER SHALL BE REMOVED BY SUCTION DREDGING. drawing 60512590-1007-10017-2, FOLLOWING THE REMOVAL OF THE BED MATERIAL, THE VOID SHALL BE Detail 1. FILLED TO THE TOP OF THE PIER FOOTING WITH C16/20 CONCRETE. CONCRETE MORTAR REPAIR Repair defects to surface of MORTAR REPAIRS TO CONCRETE SHALL BE CARRIED OUT USING FOSROC RENDEROC GP OR SIMILAR APPROVED CONCRETE previous concrete patch repairs at REINSTATEMENT MORTAR AND AS FOLLOWS: Piers 3, 4, 6 & 8 in accordance with SAW CUT OR CUT BACK EXTREMITIES OF THE REPAIR LOCATION TO A DEPTH OF AT LEAST 10mm TO AVOID FEATHER EDGING AND TO PROVIDE Concrete Repair Detail - see A SQUARE EDGE. drawing 60512590-1007-10017-2, BREAK OUT THE COMPLETE REPAIR AREA TO A MINIMUM DEPTH OF 10mm UP TO THE SAWN EDGE. Detail 1 (Photo 4). CLEAN THE SURFACE AND REMOVE ANY DUST, UNSOUND OR CONTAMINATED MATERIAL. Infill coring holes at all piers in CARE SHOULD BE TAKEN TO ENSURE THAT REPAIR MORTAR IS THOROUGHLY MIXED USING A FORCED-ACTION MIXER AND STRICTLY accordance with Concrete Mortar ADHERING TO PRODUCT MIXING INSTRUCTIONS. Repair notes. MORTAR SHOULD BE APPLIED TO SUITABLY PRIMED SUBSTRATE USING A GLOVED HAND OR TROWEL AND THOROUGHLY COMPACTED ENVIRONMENTAL CONSIDERATIONS Trim back exposed reinforcement PRIOR TO COMMENCING ANY WORKS COULD POTENTIALLY ALTER bars on North face of east abutment RIVER FLOW CHARACTERISTICS OR CAUSE DISTURBANCE TO THE RIVER BED, APPROPRIATE APPROVAL SHALL BE SOUGHT FROM THE RELEVANT (Photo 5) STATUTORY BODIES, INCLUDING BUT NOT EXCLUSIVELY; NIR, DFI RIVERS LOUGHS AGENCY, DEARA, NIEA. IF AN INVASIVE SPECIES, INCLUDING JAPANESE KNOT WEED / GIANT Remove vegetation from southern HOGWEED / HIMALAYAN BALSAM, IS IDENTIFIED OR SUSPECTED IN THE VICINITY OF THE WORK SITE, WORK SHALL BE STOPPED IMMEDIATELY face of western abutment, in AND THE APPROPRIATE BODIES, INCLUDING NIR & NIEA, SHALL BE INFORMED IMMEDIATELY. accordance with De-vegetation notes (Photo 6) Date Suffix Revision Details Purpose of issue FOR APPROVAL Translink TRANSLINK FRAMEWORK CONSULTANCY SERVICES 2016-2020 Drawing Title UNDERWATER REPAIRS 10.220 FAUGHAN RIVER Designed GTM Date JAN '18 FM URS Internal Project No. 60512590-1007 Scale @ A1 AS SHOWN THIS DOCUMENT HAS BEEN PREPARED PURSUANT TO AND SUBJECT TO THE TERMS OF AECOM'S APPOINTMENT BY ITS CLIENT. AECOM ACCEPTS NO LIABILITY FOR ANY USE OF THIS DOCUMENT OTHER THAN BY ITS ORIGINAL CLIENT OR FOLLOWING AECOM'S EXPRESS AGREEMENT TO SUCH USE, AND ONLY FOR THE PURPOSES FOR WHICH IT WAS PREPARED AND PROVIDED. Beechill House AECOM Beechill Road, Belfast BT8 7RP Tel:+44 (0)28 9070 5111 Fax:+44 (0)28 9079 5651

60512590-1007-10022-1

A1

rawing Number







S	SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION BOX IT IS ASSUMED THAT ALL WORKS ON THIS DRAWING WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROPRIATE METHOD STATEMENT.
edule of RepairsExtend or replace existing sheet piling around full perimeter of Piers 7 & 9, which have become undermined (Photos 1 & 2). Ensure sheet piles are embedded sufficiently below existing bed level to mitigate against future scour action.Once sheet piles are installed fully clutched around the full perimeter, remove loose sediment by suction 	<ul> <li>COMPLETIO CONTROLLIDAR WORKING, WHETE APPROPRIATE, TO AN APPROPRIATE IN CONTROLLIDAR OF THE PURPOSE OF ISSUE THAT IT WAS ISSUED FOR AND IS SUBJECT TO AMENDMENT.</li> <li>NOTES</li> <li>THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DOCUMENTATION.</li> <li>DO NOT SCALE FROM THIS DRAWING, USE ONLY PRINTED DIMENSIONS.</li> <li>ALL DIMENSIONS IN MILLIMETRES, ALL CHAINAGES, LEVELS AND COORDINATES ARE IN METER SUBJECT TO THE DRAWING IS TO BE READ IN CONJUNCTION WITH THE PROJECT HEALTH &amp; SAFETY FILE FOR AWI DENTIFIED DOTENTIAL RISKS.</li> <li>DEVEGETATION</li> <li>CUT BACK VEGETATION GROWTH OBSCURING FACE OF ABUTMENTS / WING WALLS / RIVER WALLS, INCLUDING AND VOETHANDING VEGETATION.</li> <li>CUT BACK VEGETATION GROWTH OBSCURING FACE OF ABUTMENTS / WING WALLS / RIVER WALLS, INCLUDING AND VOETHANDING YEGETATION.</li> <li>CUT BACK VEGETATION GROWTH OBSCURING FACE OF ABUTMENTS / WING WALLS / RIVER WALLS, INCLUDING AND VOETHANDING YEGETATION.</li> <li>CUT BACK VEGETATION GROWTH OBSCURING FACE OF ABUTMENTS / WING WALLS / RIVER WALLS, INCLUDING AND YOTE MALLED OFF SYRILLING HOLES IN ROOTS AND INJECTING WOTH A SUITABLE HERBICIDE.</li> <li>ENVIRONMENTAL CONSIDERATIONS</li> <li>PRIOR TO COMMENCING ANY WORKS COULD POTENTIALLY ALTER RIVER FLOW OF AGATE MENTS AND ROTS SILLED OFF SYRILLING HOLES IN ROOTS AND INJECTING WOTH AS UNDER WORK SCULD POTENTIALLY ALTER RIVER FLOW OF ADALTER CONSULES AND ROOTS INTO AND ROTS SILLIDANCE TO THE RIVER RED, APPROPRIATE APROVAL SHALL BE SOUGHT FROM THE RELEVANT STATUTORY BODIES, INCLUDING JAPANESE KINOT WEED (GIANT HOW REDIATELY WORK SITE, WORK SHALL BE STOPPED IMMEDIATELY AND THE YOURY DOTES, INCLUDING SING AN ISEA, SHALL BE STOPPED IMMEDIATELY AND THE YOURY OF THE WORK SITE, WORK SHALL BE STOPPED IMMEDIATELY AND THE YOURY OF THE WORK SITE, WORK SHALL BE STOPPED IMMEDIATELY AND HEAPROPRATE BODIES, INCLUDING NIR &amp; NEA, SHALL BE INFORMEDIATELY.</li> </ul>
	Revision Datails       By

30512590-1007-10022-2	
JUJ 12JJU- 1007-10022-2	

A1

Appendix C

47075660 - MLA-DS- 10.220 - Designated Sites

